

Subdivisions of T. 1 N., R. 33 E.

Chains	
40.00	West on a random line between secs. 30 and 31.
79.70	Set temporary $\frac{1}{4}$ sec. cor. Intersect West boundary, 30 lks. North of corner to secs. 30 and 31, from which I run N.89°47'E. on a true line between secs. 30 and 31.
39.70	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
79.70	The corner to secs. 29, 30, 31 and 32. Land, level. Soil, 1st rate.
40.00	North between secs. 29 and 30. Var. 19 $\frac{1}{2}$ °E.
80.00	Set stone, 16x10x8, for $\frac{1}{4}$ sec. cor. Set post for corner to secs. 19, 20, 29 and 30 in mound of earth with charred stake, pits &c as per instructions. Land, level. Soil, 2nd rate.
40.00	East on a random line between secs. 20 and 29.
79.78	Set temporary $\frac{1}{4}$ sec. cor. Intersect N. and S. line, 25 lks. South of corner to secs. 20, 21, 28 and 29, from which I run S.89°49'W. on a true line between secs. 20 and 29.
39.89	Set post for $\frac{1}{4}$ sec. corner in mound of earth with charred stake, pits &c as per instructions.
79.78	The corner to secs. 19, 20, 29 and 30. Land, level. Soil, 1st rate.
40.00	West on a random line between secs. 19 and 30.
79.92	Set temporary $\frac{1}{4}$ sec. cor. Intersect West boundary at corner to secs. 19 and 30, from which corner I run East on a true line between secs. 19 and 30.