

## Subdivisions of T. 1 N., R. 33 E.

Chains	Land, level. Soil, 1st rate.
40.00	East on a random line between secs. 5 and 8. Set temporary $\frac{1}{4}$ sec. cor.
80.17	Intersect N. and S. line at post for corner to secs. 4, 5, 8 and 9 from which I run West on a true line between secs. 5 and 8.
40.08	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
80.17	The corner to secs. 5, 6, 7 and 8. Land, level. Soil, 1st rate.
40.00	West on a random line between secs. 6 and 7. Set temporary $\frac{1}{4}$ sec. cor.
79.84	Intersect West boundary, 24 lks. South of corner to secs. 6 and 7, from which I run S.89°50'E. on a true line between secs. 6 and 7.
39.84	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
79.84	The corner to secs. 5, 6, 7 and 8. Land, level. Soil, 1st rate.
40.00	North on a random line between secs. 5 and 6. Var. $21\frac{1}{2}$ °E. Set temporary $\frac{1}{4}$ sec. cor.
79.60	Intersect North boundary, 21 lks. West of corner to secs. 5 and 6, from which I run S.0°9'W. on a true line between secs. 5 and 6.
39.60	Set post for $\frac{1}{4}$ sec. cor. in mound of earth with charred stake, pits &c as per instructions.
79.60	The corner to secs. 5, 6, 7 and 8. Land, level. Soil, 1st rate.

December 3, 1864.