

Subdivisions of T, 1 N., R. 33 E.
 Surveyed by Z.F. Moody under contract No. 145
 Dated April 23, 1871.

Chains	North between secs. 34 and 35. Var. 19° 30' East.	
40.00	Set stone, 18x14x8, for $\frac{1}{4}$ sec. corner.	
80.00	Set stone, 20x12x9, for corner to sections 26, 27, 34 and 35. Land, steep. Soil, 2nd rate, and stony.	+750
	North between secs. 26 and 27. Var. 19° East.	
31.50	Top of hill, on Western slope of mountain.	+350
40.00	Set stone, 20x20x10, for $\frac{1}{4}$ S. cor.	
80.00	Set stone, 16x15x8, for corner to secs. 22, 23, 26 and 27. Land, steep. Soil, poor, 2nd rate, very stony.	-550
	North between secs. 22 and 23. Var. 19° East.	
27.50	Foot of hill.	-450
40.00	Set stone, 30x24x18, for $\frac{1}{4}$ sec. cor.	
64.00	Top of hill.	+650
80.00	Set stone, 24x18x14, for corner to secs. 14, 15, 22 and 23. Land, steep. Soil, poor, 2nd rate, very stony.	-350
	North between secs. 14 and 15. Var. 20° East.	
19.00	Canyon, course W.	-450
40.00	Set stone, 14x12x8, for $\frac{1}{4}$ sec. corner.	
54.30	Top of hill.	+400
80.00	Set stone, 18x14x8, for corner to secs. 10, 11, 14 and 15. Land, hilly. Soil, 2nd rate. Grass, good.	-300