

Subdivisions of T. 1 N., R. 33 E.

Chains 80.20	To corner. Land, hilly. Soil, 2nd rate. Some grass. May 4, 1871.	-400
40.00 43.50 55.20 80.00	North between secs. 23 and 24. Set stone, 16x12x12, $\frac{1}{4}$ sec. corner. Brook, 3 lks. wide, flows N.W. Brook, 4 lks. wide, flows N.W. Set stone, 18x16x4, for corner to secs. 23, 24, 13 and 14.	-20 +175
40.00 80.10 40.05 80.10	East on random between secs. 13 and 24. Var. 19°30'E. Set temporary $\frac{1}{4}$ sec. cor. Intersected N. and S. line, 20 lks. S. of cor. S.89°52'W. on true line. Set basalt stone, 18x16x14, for $\frac{1}{4}$ sec. cor. To corner. Land, hilly. Soil, 2nd rate. Some good grass.	
40.00 80.08 40.04 80.08	West on random between secs. 14 and 23. Var. 19°30'E. Set temporary $\frac{1}{4}$ sec. corner. Intersected N. and S. line, 8 lks. South of corner. S.89°57'E. on true line. Set basalt stone, 16x14x7, for $\frac{1}{4}$ sec. corner. To corner. Land, hilly. Soil, 2nd rate. Some grass.	+300 +100