

Base Line of T. 1 N., R. 33 E.

Chains	of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
44.00	Summit of ridge.	
46.00	Gulch, course S.	-100
68.00	Summit bears S.	+300
80.00	Set basalt stone, 16x12x10 ins., 10 ins. in the ground for cor. to secs. 33 and 34 marked S C with 3 notches on E. and W. edges. Dug pits, 18x18x12 ins., N. E. and W. of stone, $5\frac{1}{2}$ ft. dist. and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.	
	Land, rough and mountainous. 80 chs.	
	Soil, 2nd rate. Good grass.	
	Thence S.89°51'West on true line S. bdy. sec. 33 Var. 20°East.	
20.75	Gulch, South.	-200
30.00	Summit.	+200
40.00	Set basalt stone, 12x10x8 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor. marked S C $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins. E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised mound of earth, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
47.25	Small bluff of rock.	+12
63.00	Ravine or gulch, course S.E.	-50
77.00	Summit of ridge, S.	+400
80.00	Set basalt stone, 18x14x10 ins., 12 ins. in the ground for cor. to secs. 32 and 33 marked S C with 4 notches on E. and 2 notches on W. edges, and raised mound stone 2 ft. high, $4\frac{1}{2}$ ft. base over it.	
	Land, rough, mountainous and rocky. 80 chs.	
	Soil, poor. Grass, fair.	
	Thence S.89°51'W. on true line, S. bdy. sec. 32. Var. 21 $\frac{1}{2}$ °East.	
25.00	Dry gulch, course S.	-200
36.50	Summit hill.	+300
40.00	Set basalt stone, 16x9x7 ins., 10 ins. in the ground for $\frac{1}{4}$ sec. cor. marked S C $\frac{1}{4}$ on N. face. Dug pits, 18x18x12	