

Exteriors of T. 1 N., R. 33 E.
 Surveyed by Currin and Noland under special contract.
 Dated May 4, 1887.

(East Boundary)

Chains		
	Beginning on Base Line at cor. to Tps. 1 N., Rs. 33 and 34 East I run.	
	N. on E. bdy. sec. 36.	
	Var. $20^{\circ}30'E$.	
	Ascend ridge.	
40.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Raised a md. of stone alongside. Pits impracticable.	+200
80.00	Set basalt stone, 12x9x7 ins., 8 ins. in the ground for cor. to secs. 25, 30, 31 and 36, marked 1 notch on S. and 5 on N. edges. Raised a mound of stone alongside. Pits impracticable.	+700
	Land, mountainous. 80 chs.	
	Line runs up sharp ridge.	
	Soil, rocky, 4th rate. No timber.	
	Grass, poor.	
	North on E. bdy. sec. 25.	
	Var. $27^{\circ}E$.	
1.00	Descend.	
14.00	Ravine, course W.	-300
35.00	Summit of ridge, course SE.	+400
40.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Raised stone md. alongside. Pits impracticable.	
75.00	Table land.	+250
80.00	Set a basalt stone, 12x9x7 ins., 8 ins. in the ground for cor. to secs. 19, 24, 25 and 30, marked 2 notches on S. and 4 on N. edges. Dug pits, 18x18x12 ins., in each sec. $5\frac{1}{2}$ ft. dist. Raised earth md. 2 ft. high, $4\frac{1}{2}$ ft. base alongside.	
	Land, rough and mountainous. 75 chs.	
	Soil, rocky, 4th rate, barren except table land which is 1st rate covered with thick growth bunch grass and sun flower.	