

Subdivisions of T. 1 N., R. 33 E.

Chains	<p>on S. and 1 notch on E. edges and raised mound of stone over it. Pits impracticable.</p> <p>Land, rough and mountainous. 80 chs.</p> <p>Soil, generally good except on S. hillsides which are rocky. Bunch grass.</p>	
	<p>East on random between secs. 1 and 12.</p> <p style="text-align: center;">Var. 20° East.</p> <p>40.00 Set temporary $\frac{1}{4}$ sec. cor. and at</p> <p>79.54 Intersect E. bdy. Township, 64 lks. N. of cor. to secs. 1, 12, 6 and 7. Thence N. 89° 32' W. on true line between secs. 1 and 12.</p> <p style="text-align: center;">Var. 19 $\frac{3}{4}$° East.</p>	
	<p>Descend.</p>	
30.50	<p>Canyon, N.W.</p>	-600
	<p>Ascend.</p>	
39.77	<p>Set basalt stone, 9x8x8 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5$\frac{1}{2}$ ft. dist. and raised mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it.</p>	+400
	<p>Descend.</p>	
40.80	<p>Small gulch, N.E.</p>	-20
	<p>Ascend.</p>	
54.00	<p>Top of ridge, N.W.</p>	+500
	<p>Descend.</p>	
79.54	<p>Cor. to secs. 1, 2, 11 and 12.</p> <p>Land, rough and mountainous. 79.54 chs.</p> <p>Soil, 3rd rate. Good grass.</p>	
	<p>North on random between secs. 1 and 2.</p>	
	<p style="text-align: center;">Var. 20° East.</p>	
	<p>Set temporary $\frac{1}{4}$ and 1/16 sec. cors. at 20, 40 and 60</p>	
	<p>chains and at</p>	
79.20	<p>Intersect Tp. line, 62 lks. E. of cor. to secs. 1, 2, 35 and 36. Thence</p>	