

Subdivisions of T. 1 N., R. 33 E.

Chains	Descend.	
40.00	Set basalt stone, 12x10x5 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
44.00	Gulch, S.W.	-150
58.00	Summit, S.W.	+200
65.00	Gulch, W.	-150
68.50	Summit hill, W.	+60
71.60	Gulch, W.	-100
80.00	Set basalt stone, 16x14x12 ins., 10 ins. in the ground for cor. to secs. 22, 23, 26 and 27 marked with 2 notches on S. and E. edges. Raised mound of stone 2 ft. high, $4\frac{1}{2}$ ft. base over it. Pits impracticable. Land, very rough and mountainous. 80 chs. Soil, 4th rate rocky. Little bunch grass.	
	East on random between secs. 23 and 26. Var. $21\frac{1}{2}^{\circ}$ E.	
79.75	Set temporary $\frac{1}{4}$ sec. cor. and at Intersect E. bdy. 21 lks. N. of cor. to secs. 23, 24, 25 and 26. Thence N. $89^{\circ}51'$ W. on true line between secs. 23 and 26. Var. 23° East.	
12.75	Gulch, N.	-300
28.00	Summit ridge, N.	+300
39.87	Set basalt stone, 14x12x10 ins., 9 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, raised mound of earth and stone, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
41.05	Gulch, N.	-200
52.00	Summit ridge, N.	+200
79.75	Cor. to secs. 22, 23, 26 and 27. Land, rough and mountainous. 79.75 chs. Soil, 2nd rate. Grass, good.	