

## Subdivisions of T. 1 N., R. 33 E.

|        |  |      |
|--------|--|------|
| Chains | North between secs. 22 and 23.   |      |
|        | Var. $21\frac{1}{2}^{\circ}$ E.  |      |
| 29.00  | Top of hill or ridge, W.   | +400 |
| 38.00  | Ravine.  | -300 |
| 40.00  | Set stone, 9x8x7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec.<br>cor. marked $\frac{1}{4}$ on W. face, raised mound of stone, $1\frac{1}{2}$ ft.<br>high, $3\frac{1}{2}$ ft. base over it. Pits impracticable.  |      |
| 53.00  | Ravine and trail bears S.W.  | -100 |
| 80.00  | Set post, 4 ft. long, 4 ins. square, 24 ins. in the ground,<br>for corner to secs. 14, 15, 22 and 23 marked T 1 N S 14<br>on N.E., R. 33 E S 23 on S.E., S 22 on S.W. and S 15 on<br>N.W., with 3 notches on S. and 2 notches on E. edges.<br>Dug pits, 18x18x12 ins., in each sec. $5\frac{1}{2}$ ft. dist.,<br>raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base around<br>post.<br>Land, mountainous. 80 chs.<br>Soil, 1st rate. Good grazing land. |      |
|        | East on random between secs. 14 and 23.  |      |
|        | Var. $22^{\circ}$ East.  |      |
| 40.00  | Set temporary $\frac{1}{4}$ sec. cor. and at   |      |
| 80.00  | Intersect N. and S. line, 28 lks. N. of cor. to secs. 13,<br>14, 23 and 24. Thence<br>N. $89^{\circ}48'$ W. on true line between secs. 14 and 23.  |      |
|        | Var. $22^{\circ}$ E.   |      |
| 17.50  | Gulch and trail, N.W.  | -200 |
| 22.00  | Summit, N.W.   | +100 |
| 40.00  | Set basalt stone, 9x8x7 ins., 6 ins. in the ground for $\frac{1}{4}$<br>sec. cor. marked $\frac{1}{4}$ on N. face, raised mound of stone<br>alongside. Pits impracticable.   |      |
| 40.75  | Canyon, N.W.   | -400 |
| 44.50  | Ravine, N.   | -100 |
| 60.00  | Summit, N.   | +200 |
| 74.00  | Ravine, N.   | -150 |
| 80.00  | Cor. to secs. 14, 15, 22 and 23.   |      |