

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 28
	raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
63.00	Road, course S.E.
79.71	The corner to secs. 28, 29, 32 and 33. Land, rolling. Soil, 1st rate. Good grass. June 20, 1889.
	North between secs. 28 and 29. Var. $21^{\circ}30'E$.
10.00	Creek, 2 lks. wide, course N.W.
20.00	Set basalt stone, 14x8x5 ins., 10 ins. in the ground, for $1/16$ sec. corner marked $1/16$ on W. face, and raised mound of stone over it. Pits impracticable.
23.50	Top of Rimrock.
40.00	To the $\frac{1}{4}$ sec. corner, which is a stone, 12x12x10 ins., 8 ins. in the ground marked $\frac{1}{4}$ on W. face. Pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist., and mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
60.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for $1/16$ sec. corner marked $1/16$ on W. face, and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
80.00	To corner to secs. 20, 21, 28 and 29. Land, rolling. Soil, 1st and 2nd rate. Grass.
	From the $1/16$ sec. corner, 20 chs. W. of the corner to secs. 21, 22, 27 and 28. I run South on true line in sec. 28. Var. $19^{\circ}30'E$.
10.00	Ascend to Summit, course W. Descend.