

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 28
20.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face, and raised mound of stone over it. Pits impracticable.
23.00	Trail in Gulch, course W. Ascend.
40.00	Set basalt stone, 12x10x7 ins., 8 ins. in the ground, on steep hillside, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it. Land, mountainous. Soil, 1st rate on N. hillside, rocky on S. hillside. Good bunch grass.
60.00	From the ¼ sec. corner between secs. 28 and 29. I run S.89°35'E. on random line in the center of sec. 28. Var. 20°E. Setting temporary corners at 20 and 40 chains, and at Intersect the N. and S. line, 15 lks. South of the 1/16 sec. cor. Thence I run N.89°43'W. on true line in the center of sec. 28. Var. 20°East.
20.00	Along side hill to Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for ¼ sec. corner marked ¼ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it. Descend.
30.00	Trail, course S.W.
40.00	Set basalt stone, 12x8x7 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face, and raised a mound of stone over it. Pits impracticable. Descend to