

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 29
	From the 1/16 sec. corner, 20 chs. N. of the 1/4 sec. corner between 29 and 30.
	I run
	N.89°55'E. on random line through N.1/2 of sec. 29.
	Var. 20°30' East.
	Setting temporary corners at 20, 40 and 60 chains, and at
79.84	Intersect the N. and S. line, 15 lks. South of the 1/16 sec. cor. between secs. 28 and 29.
	Thence I run
	S.89°49'W. on true line through the N.1/2 of sec. 29.
	Var. 20°E.
8.00	Gulch and ditch, course N.W.
19.20	Road, course N.W.
19.96	Set basalt stone, 12x8x6 ins., 8 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 1/2 ft. dist., and raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.
39.92	Set basalt stone, 10x9x6 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 1/2 ft. dist., and raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.
59.88	Set basalt stone, 12x9x6 ins., 8 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 1/2 ft. dist., and raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.
79.84	To the 1/16 sec. corner between secs. 29 and 30.
	Land, mostly level.
	Very little grass.
	Soil, ashy.
	From the corner to secs. 29, <sup>Sec. 30</sup> 30, 31 and 32.
	I run
	West on true line between secs. 30 and 31.
	Var. 20° East.