

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 30
	<p>Thence I run</p> <p>S.89°57'E. on true line through S. $\frac{1}{2}$ of sec. 30.</p> <p style="text-align: center;">Var. 20°E.</p>
18.20	<p>Set basalt stone, 9x9x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.</p>
38.20	<p>Set basalt stone, 10x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face, and raised mound of stone over it. Pits impracticable.</p>
58.20	<p>Set basalt stone, 10x7x6 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.</p>
78.20	<p>To the 1/16 sec. corner between secs. 29 and 30.</p> <p>Land, mostly level.</p> <p>Soil, 2nd rate.</p> <p>Very little grass.</p>
	<p>From the $\frac{1}{4}$ sec. corner between secs. 29 and 30.</p> <p>I run</p> <p>West on random through the center of sec. 30.</p> <p style="text-align: center;">Var. 20°East.</p> <p>Setting temporary corner at 20, 40 and 60 chains and at</p>
78.30	<p>Intersect the W. boundary of Tp., 25 lks. N. of $\frac{1}{4}$ sec. corner on W. bdy. of sec. 30.</p> <p>Thence I run</p> <p>N.89°49'E. on true line through the center of sec. 30.</p> <p style="text-align: center;">Var. 20°E.</p>
18.30	<p>Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.</p>