

## Subdivisions of T. 1 N., R. 33 E.

Chains 50.00	Ravine, N.	-10
79.75	Cor. to secs. 10, 11, 14 and 15. Land, rolling. 29.75 chs. Mountainous, 50 chs. Soil, good. Bunch grass.	
	North between secs. 10 and 11. Var. 22° East..	
20.00	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on W. face.	
40.00	Set stone, 12x10x8 ins., 8 ins. in the ground for ¼ sec. cor. marked ¼ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it. Descend gradually.	
60.00	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on W. face.	
79.50	Dry creek bed, N.W.	
80.00	Set stone, 16x16x14 ins., 10 ins. in the ground for cor. to secs. 2, 3, 10 and 11, marked with 5 notches on S. and 2 notches on E. edges, from which A balm, 14 ins. diam., bears S.70°E., 80 lks. dist., marked T 1 N R 33 E S 11 B T. A balm, 10 ins. diam., bears S.45°W., 57 lks. dist., marked T 1 N R 33 E S 10 B T. A balm, 16 ins. diam., bears N. 88° W., 20 lks. dist., marked T 1 N R 33 E S 3 B T. No other trees within limits. Raised mound of stone alongside. Pits impracticable.	