

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 32
	Thence I run N.89°54'W. on true line through S. $\frac{1}{2}$ .of sec. 32. Var. 20°10' E.
	Descend Mt. to
19.96	Set basalt stone, 10x8x6 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it..
29.50	Trail, course N.E.
34.00	Trail, course W.
39.92	Set basalt stone, 11x8x5 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
45.00	Gulch, course N.W., flat.
59.88	Set basalt stone, 10x8x5 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
79.85	To the 1/16 sec. corner between secs. 31 and 32. Land, rolling. Soil, 1st and 2nd rate. Good grass in E. part.
	From the $\frac{1}{4}$ sec. corner between secs. 31 and 32. I run East on random line through the center of sec. 32. Var. 20° E. Setting temporary corner at every 20, 40 and 60 chains, and at
80.00	Intersect the N. and S. line, 15 lks. N. of $\frac{1}{4}$ sec. corner between secs. 32 and 33. Thence I run N.89°54'W. on true line through the center of sec. 32. Var. 20°30'E.