

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 32
20.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12, E. and W. of stone, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it.
28.50	Flat Gulch, course N.W.
40.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
60.00	Set basalt stone, 9x7x8 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., raised a mound of earth 1½ ft. high, 3½ ft. base over it.
80.00	To the 1/16 sec. corner between secs. 31 and 32. Land, level plains. Soil, 2nd rate. Same grass.
Sec. 33	
From the corner to secs. 27, 28, 33 and 34.	
I run	
South on true line between secs. 33 and 34.	
Var. 20° East.	
.20	Dry creek bed, course W.
4.50	Gulch, course N.W.
Ascend to	
20.00	Set basalt stone, 11x8x6 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., raised a mound of earth 1½ ft. high, 3½ ft. base over it.
Thence I run	
N.89°30'W. on random line through the N.½ of sec. 33.	
Var. 21° E.	
Setting temporary corner at every 20, 40 and 60 chains, and at	