

## Subdivisions of T. 1 N., R. 33 E.

Chains		
40.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
41.50	Gulch, S.W.	-150
48.00	Summit ridge, W.	+300
64.00	Gulch, W.	-250
72.00	Gulch, W.	-100
	Ascend.	
80.00	Set basalt stone, 18x18x12 ins., 12 ins. in the ground, for cor. to secs. 21, 22, 27 and 28 marked with 2 notches on S. and 3 notches on E. edges. Raised mound of stone, 2 ft. high, $4\frac{1}{2}$ ft. base over it. Pits impracticable.	
	Land, rough and mountainous. 80 chs.	
	Soil, 1st rate; and good grass.	
	East on random between secs. 22 and 27.	
	Var. $20^{\circ}$ East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
79.76	Intersect E. bdy. 42 lks. N. of cor. to secs. 22, 23, 26 and 27. Thence N. $89^{\circ}42'W.$ on true line between secs. 22 and 27.	
	Var. $21\frac{1}{2}^{\circ}$ East.	
24.85	Gulch, N.	-100
39.94	Set basalt stone, 9x8x7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face and dug pits 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist. and raised mound of earth and stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
43.30	Gulch, N.	-100
79.76	Cor. to secs. 21, 22, 27 and 28.	
	Land, rolling.	
	Soil, 1st rate. Grass, good.	