

Subdivisions of T. 1 N., R. 33 E.

Chains	
	S. 48' East on true line between secs. 4 and 5. Var. 20° East.
1.00	Trail, N.W.
16.80	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.
35.00	Wagon road, N.W.
36.80	Set post, 3 ft. long, 3 ins. square, 24 ins. in the ground for ¼ sec. cor. marked ¼ S on W. face. Dug pits, 18x18x12 ins., N. and S. of post, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base around it.
50.00	Dry bed of creek, N.W.
56.80	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, 5½ ft., raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W. face.
76.80	Cor. to secs. 4, 5, 8 and 9. Land, level. Soil, 1st rate. Grass, good. August 2, 1887.
	From cor. to secs. 31 and 32 on S. bdy. of Tp. I run North between secs. 31 and 32. Var. 18°10' East.
39.60	Gulch, N.W.
40.00	Set basalt stone, 12x10x8 ins., 8 ins. in the ground for ¼ sec. cor. marked ¼ on W. face and raised mound of stone 1½ ft. high, 3½ ft. base over it.
73.50	Trail, S.W.
80.00	Set stone, 10x8x8 ins., 6 ins. in the ground, for cor. to secs. 29, 30, 31 and 32 marked with 1 notch on S. and 5 notches on E. edges. Dug pits, 18x18x12 ins., in