

## Subdivisions of T. 1 N., R. 33 E.

Chains	of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
40.60	Gulch, N.W.	-20
51.00	Gulch, N.W.	-25
80.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for cor. to secs. 7, 8, 17 and 18 marked with 4 notches on S. and 5 notches on East edges. Dug pits, 18x18x12 ins., in each sec. $5\frac{1}{2}$ ft. dist. and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it. Land, level or nearly so. Soil, 1st rate. Very little grass. Uncultivated.	
	East on random between secs. 8 and 17. Var. 22° East. Set temporary $\frac{1}{4}$ and $1/16$ sec. cors. at 20, 40 and 60 chains and at	
80.04	Intersect N. and S. line, 28 lks. N. of cor. to secs. 8, 9, 16 and 17. Thence N. 89°48'W. on true line between secs. 8 and 17. Var. 20° East.	
20.01	Deposited charred stake, 12 ins. in the ground, for $1/16$ sec. cor. Dug pits, 18x18x12 ins., E. and W. of cor. $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $1/16$ S on N. face.	
40.02	Set basalt stone, 12x10x10 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
60.03	Deposited charred stake, 12 ins. in the ground for $1/16$ sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $1/16$ S on N. face.	
80.04	Cor. to secs. 7, 8, 17 and 18.	