

Subdivisions of T. 1 N., R. 33 E.

Chains	North between secs. 7 and 8. Var. 22° East.
14.75	Trail, E. and W.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W. face.
22.20	Draw, W.
23.05	Trail, N.W.
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor. Dug pits, 18x18x12 ins. N. and S. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked ¼ S on W. face.
41.00	Trail, W.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., N. and S. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W. face.
80.00	Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to secs. 5, 6, 7 and 8 marked T 1 N S 5 on N.E., R 33 E S 8 on S.E., S 7 on S.W. and S 6 on N.W. with 5 notches on S. and E. edges. Dug pits, 18x18x12 ins., in each sec. 5½ ft. dist. and raised mound of earth 2 ft. high, 4½ ft. base over it. Land, level. Soil, 1st rate. Very little grass.
	East on random between secs. 5 and 8. Var. 20½° E. Set temporary ¼ and 1/16 sec. cors. at 20, 40 and 60 chains and at

-20