

Subdivisions of T. 1 N., R. 33 E.

Chains 80.00	Intersect N. and S. line, 35 lks. N. of cor. to secs. 4, 5, 8 and 9. Thence N.89°45'W. on true line between secs. 5 and 8. Var. 20½° East.
20.00	Set basalt stone, 9x8x8 ins., 6 ins. in the ground for 1/16 sec. cor. marked 1/16 on N. face. Dug pits, 18x18x12 ins. E. and W. of stone, 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base alongside.
40.00	Set basalt stone, 12x18x7 ins., 8 ins. in the ground for ¼ sec. cor. marked ¼ on N. face and dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it.
60.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. cor. marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base over it.
80.00	Cor. to secs. 5, 6, 7 and 8. Land, level. Soil, 1st rate. Grass scarce. Not cultivated.
	West on true line between secs. 6 and 7. Var. 20° East.
20.00	Deposited charred stake 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face.
40.00	Set post, 3 ft. long, 3 ins. square, 24 ins. in the ground, for ¼ sec. cor. marked ¼ S on N. face. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base over it.
60.00	Set basalt stone, 10x8x7 ins., 6 ins. in the ground in ✓