

Subdivisions of T. 1 N., R. 33 E.

Chains 56.42	Trail, W.
76.00	Cor. to secs. 5, 6, 7 and 8. Land, gently rolling. Grass, scarce. Soil, 1st rate. August 3, 1887.
General Description	
<p>The Eastern part of this Township is heavy mountainous cut by deep canyons running to the West. The South and West faces of mountains and hill are very rocky, while the North and East slopes are a rich black loam. No timber except a little pine in canyons in S.E. portion.</p> <p>The Western part which comprises perhaps a little more than half of the Township is level or gently rolling. No timber.</p> <p>The bunch grass has been good in this Township and there is still considerable in the mountainous part but in the level and rolling part it is about all killed out by grazing.</p>	
<p>Sub-Subdivisions of T. 1 N., R. 33 E. Surveyed by Currin and Noland under special contract. Dated May 4, 1887.</p>	
<p>Commencing at 1/16 sec. cor., 20 chains N. of S.W. cor. of sec. 10.</p>	
<p>East on random through $S\frac{1}{2}$ of sec. 10.</p>	
<p>Var. 20° East.</p>	
<p>Set temporary 1/16 sec. cors. at 20, 40 and 60 chains, and at</p>	
79.50	<p>Intersect N. and S. line, 42 lks. N. of 1/16 sec. cor. Thence N.89°42'W. on true line.</p>
<p>Var. same.</p>	
19.88	<p>Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
39.76	<p>Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>