

Sub-Subdivisions of T. 1 N., R. 33 E.

Chains 59.64	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in the E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
79.50	1/16 sec. cor. Land, level. Soil, 2nd rate. No grass.
	Commencing at ¼ sec. cor. between secs. 9 and 10 I run a random line East through center of sec. 10. Var. 21° East. Set temporary ¼ and 1/16 sec. cors. at 20, 40 and 60 chains and at
79.45	Intersect E. bdy. 42 lks. N. of ¼ sec. cor. Thence N. 89° 42' W. on true line. Var. same.
19.86	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. cor. marked 1/16 on N. face and raised mound of stone over it.
39.73	Deposited charred stake, 12 ins. in the ground for ¼ sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S on N. face.
59.59	Set basalt stone, 12x8x6, 8 ins. in the ground, for 1/16 sec. cor. marked 1/16 on N. face. Dug pits, E. and W. of stone, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it.
60.00	Dry bed of creek, N.
79.45	¼ sec. cor. between secs. 9 and 10. Land, level. Soil, 2nd rate. No grass.