

## Sub-Subdivisions of T. 1 N., R. 33 E.

Chains 79.85	Intersect E. bdy., 25 lks. N. of 1/16 sec. cor. Thence N.89°49'W. on true line.  Var. same.
19.96	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., East and West of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
39.93	Set basalt stone, 12x8x6 ins., 8 ins. in the ground, for 1/16 sec. cor. marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base over it.
40.00	Dry bed of creek, N.W.
59.89	Deposited marked stone, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 12 ins. in the ground marked 1/16 S on N. face.
79.85	1/16 sec. cor. between secs. 2 and 3. Land, rolling. Soil, 1st rate. Grass, fair.  October 28, 1887.
	East on random through center of sec. 2.  Var. 20° East.  Commencing at ¼ sec. cor. between secs. 2 and 3. Set temporary ¼ and 1/16 sec. cors. at 20, 40 and 60 chains and at
79.90	Intersect E. bdy., 25 lks. N. of ¼ sec. cor. between secs. 1 and 2. Thence N.89°49'W. on true line. Var. same.
1.00	Summit ridge and descend.
19.97	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft.