

Sub-Subdivisions of T. 1 N., R. 33 E.

Chains	
	base over it and in E. pit drove stake 2 ft. long, 12 ins. in the ground and 2 ins. square marked 1/16 S on N. face.
59.64	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of cor., 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
79.55	1/16 sec. cor. between secs. 3 and 4.
	Land, level.
	Soil, 1st rate.
	Grass grazed off closely.
	East on random through center of sec. 3.
	Var. 21° East.
	Commencing at ¼ sec. cor. between secs. 3 and 4, set temporary ¼ and 1/16 secs. cors. at 20, 40 and 60 chains and at
79.70	Intersect E. bdy., 50 lks. N. of ¼ sec. cor. between secs.
	2 and 3. Thence
	N.89°39'W. on true line.
	Var. 20° East.
19.75	Dry ditch N.W.
19.92	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for
	1/16 sec. cor. marked 1/16 on N. face. Dug pits,
	18x18x12 ins., E. and W. of stone, 5½ ft. dist., raised
	mound of earth 1½ ft. high, 3½ ft. base over it.
39.85	Deposited charred stake 12 ins. in the ground for ¼ sec.
	cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft.
	dist., raised mound of earth 1½ ft. high, 3½ ft. base
	over it, and in E. pit drove stake 2 ft. long, 2 ins.
	square, 12 ins. in the ground marked ¼ S on N. face.
59.77	Deposited charred stake 12 ins. in the ground for 1/16
	sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake,
	5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft.
	base over it and in E. pit drove stake 2 ft. long, 2 ins.
	square, 12 ins. in the ground marked 1/16 S on N. face.