

Sub-Subdivisions of T. 1 N., R. 33 E.

Chains	
25.75	Tudie Willows creek, 4 lks., course N.
39.97	Deposited charred stake, 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S on N. face.
59.96	Deposited charred stake, 12 ins. in the ground, for 1/16 sec. cor. Dug pits, 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
75.00	Dry ditch, course N.E.
79.95	$\frac{1}{4}$ sec. cor. between secs. 4 and 5. Land, level. Soil, 1st rate. Poor grass.
	East on random through N. $\frac{1}{2}$ of sec. 4. Var. 21° East. Commencing at 1/16 sec. cor., 20 chains N. of $\frac{1}{4}$ sec. cor. between secs. 4 and 5. Set temporary 1/16 sec. cors. at 20, 40 and 60 chains and at
79.92	Intersect E. bdy, 50 lks. N. of 1/16 sec. cor. between secs. 3 and 4. Thence N.89°39'W. on true line. Var. same.
19.98	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
36.50	Tudie Willows creek, course N.W., dry.
39.96	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft.