

## Sub-Subdivisions of T. 1 N., R. 33 E.

Chains	<p>5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>	-20
75.00	Gulch, course N.W.	
80.00	<p>1/16 sec. cor. between secs. 8 and 9. Land, mostly level. Soil, 1st rate. Grass very light.</p>	
East on random through center of sec. 8.		
Var. 21½° East.		
Commencing at ¼ sec. cor. between secs. 7 and 8.		
Set temporary ¼ and 1/16 sec. cors. at 20, 40 and 60 chains and at		
80.04	<p>Intersect E. bdy., 25 lks. N. of ¼ sec. cor., between secs. 8 and 9. Thence N.89°49'W. on true line.</p>	
Var. 20½° East.		
20.01	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.</p>	
40.02	<p>Deposited charred stake, 12 ins. in the ground for ¼ sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked ¼ S on N. face.</p>	
60.03	<p>Deposited charred stake 2 ft. long, 2 ins. square, 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.</p>	