

Sub-Subdivisions of T. 1 N., R. 33 E.

Chains 26.00	Wagon road, course N.
40.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits, 18x18x12 ins., E. and W. of stake, 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
77.04	Intersect W. bdy. Township, 15.00 chains S. of Township cor. to 1 and 2 N., Rgs. 32 and 33 and deposited charred stake 12 ins. in the ground for closing 1/16 sec. cor. Dug pits, 18x18x12 ins., N. E. and S. of stake, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 C C on E. face.

Land, slightly rolling.

Soil, generally 1st rate. Not cultivated.

Very light grass.

November 2, 1887.

General Description

The sections subdivided constitute a body of gently rolling and level land, general slope to the West. There is very little rock and no timber on it. The soil is very nearly all rich and fit for cultivation. The original heavy crops of bunch grass are about all killed out by stock. There is very little grass on the land and of an inferior quality.

October 31, 1887.