

Subdivisional and Allotment Lines of
 T. 1 N., R. 33 E.
 Surveyed by James P. Currin under contract No. 537.
 Dated March 5, 1889.

Chains	Sec. 11
	From the 1/16 sec. corner, 20 chains West of the corner to secs. 1, 2, 11 and 12, which is a basalt stone, 9x8x7 ins., 6 ins. in the ground, marked 1/16 on N. face with mound of stone over it. I run South on true line in sec. 11. Var. 19° East.
1.50	Gulch, course N.W. and ascend.
20.00	Set a basalt stone, 12x8x7 ins., 8 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it. Land. Soil, 1st rate. Good grass.
	From the 1/16 sec. corner, 20 chs. South of the corner to secs. 2, 3, 10 and 11, which is a charred stake with pits, 18x18x12 ins., N. and S. of stake, 5½ ft. dist., and a mound of earth over it and in N. pit a stake, 2 ins. square, firmly set in the ground marked 1/16 S. on W. face. I run S.89°49'E. on random line through section 11. Var. 20° E.
	Setting temporary 1/16 sec. corner at every 20 chains and at
59.95	Intersect the 1/16 sec. corner, 20 chains S. of the line between secs. 2 and 11 at corner. Thence I run N.89°49'W. on true line through sec. 11. Var. same.
15.30	Trail, course N.E.
19.98	Set basalt stone, 12x9x8 ins., 8 ins. in the ground, for 1/16 sec. corner, marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base over it.
29.00	Summit, course N.W. Descend.