

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	<p style="text-align: center;">Sec. 11</p> <p>raised a mound of stone over it, marked 1/32 on N. face for 1/32 sec. corner. Pits impracticable.</p> <p>Land on hillside.</p> <p>Soil, 1st rate and rocky.</p> <p>Grass and weeds.</p>
19.96	<p>From the $\frac{1}{4}$ sec. corner on West bdy. of sec. 11, which is a stone, 12x10x8 ins., 8 ins. in the ground, marked $\frac{1}{4}$ on W. face with pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist., and mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p> <p>Thence I run</p> <p>S.89°49'E. on random line through sec. 11.</p> <p style="text-align: center;">Var. 19° E.</p>
39.95	<p>Set temporary 1/16 sec. corner.</p> <p>Intersect the N. and S. line at $\frac{1}{4}$ sec. corner in the center of sec. 11.</p> <p>Thence I run</p> <p>N.89°49'W. on true line through sec. 11.</p> <p style="text-align: center;">Var. 19°E.</p>
3.00	<p>Tudie Willow Creek, 3 lks. wide, course N.W.</p>
19.97	<p>Set basalt stone, 12x8x6 ins., 8 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p>
24.00	<p>Ascend.</p>
39.95	<p>To $\frac{1}{4}$ sec. corner between secs. 10 and 11.</p> <p>Land, rolling and level in bottom.</p> <p>Soil, mostly 1st rate.</p> <p>Grass and weeds.</p>
	<p>From the 1/16 sec. corner, 19.97 chains East of $\frac{1}{4}$ sec. corner between secs. 10 and 11.</p> <p>I run</p> <p>North on true line in sec. 11.</p> <p style="text-align: center;">Var. 19°E.</p>