

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	<p style="text-align: center;">Sec. 15.</p> <p>3 notches on S. and E. edges. Pits, 18x18x12 ins., in each sec., 5½ ft. dist. and mound of earth 2 ft. high, 4½ ft. base over it.</p>
	<p>I run North between secs. 15 and 16.</p>
	Var. 20°E.
20.00	<p>Set stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. cor., marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it.</p>
25.00	Ditch, course N.W.
40.00	<p>The old ¼ sec. corner, which is a charred stake and pits, 18x18x12 ins., N. and S. of stake, 5½ ft. dist., and mound of earth 1½ ft. high, 3½ ft. base over it. In N. pit, a stake, 12 ins. above ground, 2 ins. square, marked ¼ S on W. face.</p>
60.00	<p>Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner, marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.</p>
80.00	<p>The corner to secs. 9, 10, 15 and 16, which is a basalt stone, 10x10x6 ins., 6 ins. in the ground, marked with 4 notches on S. and 3 notches on E. edges, with pits, 18x18x12 ins., in each sec., 5½ ft. dist., and mound of earth, 2 ft. high, 4½ ft. base over it.</p>
	<p>Land, gently rolling. Soil, 1st rate. Fine grass and weeds. Well adapted to agriculture.</p>
	<p>From the 1/16 sec. cor., 20 chains N. of ¼ sec. corner, between secs. 15 and 16.</p>
	<p>Thence I run S.89°43'E. on random line through the N½ of sec. 15.</p>
	Var. 20°E.