

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 16
	Pits impracticable.
67.00	Gulch, course N.W.
76.00	Wagon road, course N. and S.
80.00	The corner to secs. 15, 16, 21 and 22. Land, rolling. Soil, 1st and 2nd rate. Good grass.
North between secs. 16 and 17.	
Var. 23° East.	
16.00	Ditch, course W.
20.00	Set basalt stone, 10x7x7 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
40.00	The old ¼ sec. corner, which is a basalt stone, 12x10x6 ins., 8 ins. in the ground, marked ¼ on W. face with pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and mound of earth 1½ ft. high, 3½ ft. base over it.
60.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
72.00	Dry bed of creek, course N.W.
80.00	The corner to secs. 8, 9, 16 and 17, which is a post, 4 ins. square, firmly set in the ground, marked T 1 N S 9 on N.E., R. 33 E S 16 on S.E., S 17 on S.W. and S 8 on N.W. faces, with 4 notches on S. and E. edges, with pits, 18x18x12 ins., in each sec., 5½ ft. dist., and mound of earth 2 ft. high, 4 ft. base around post. I obliterated the letters D R on post. Land, rolling, Soil, 1st rate. Grass, good.