

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 16
	From the 1/16 sec. corner, 20 chains N. of corner to secs. 16, 17, 20 and 21.
	I run
	S.89°44'E. on random line through the S.½ of sec. 16.
	Var. 22°E.
	Setting temporary 1/16 sec. corner at 20, 40 and 60 chains and at
80.00	Intersect the East bdy. of sec. 16 at 1/16 sec. corner. Thence I run
	N.89°44'W. on true line through sec. 16.
	Var. 21°30'E.
11.00	Gulch, course N.W.
17.75	Gulch, course N.W.
20.00	Set a basalt stone, 10x8x7, 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face, and raised a mound of stone over it. Pits impracticable.
27.00	Ditch, course N.W.
39.95	" " "
40.00	Set a basalt stone, 10x8x6 ins., 7 ins. in the ground, for 1/16 sec. corner, marked 1/16 on N. face and raised mound of stone over it. Pits impracticable.
47.60	Road, course N. and S.
55.50	Flat gulch, course N.W.
60.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, and 3½ ft. base over it.
80.00	To 1/16 sec. corner. Land, rolling. Soil, 1st rate. Good grass.
	From the ¼ sec. corner between secs. 16 and 17.
	I run
	S.89° 44' E. on random line through the center of sec. 16.
	Var. 20°E.