

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	<p style="text-align: center;">Sec. 17</p> <p>raised a mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it.</p>
52.00	Road, course N.78°W.
80.10	To the 1/16 sec. corner between secs. 17 and 18. Land, level or gently rolling. Soil, 2nd rate. Weeds and grass.
	Sec. 18
	West between secs. 18 and 19.  Var. 21°E.
20.00	Deposited charred stake 12 ins. in the ground, for 1/16 sec. corner. Dug pits, 18x18x12 ins., E. and W. of stake, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. In E. pit drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
25.00	Descend hill.
40.00	The old $\frac{1}{4}$ sec. corner, which is a basalt stone, 12x12x12 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. corner marked $\frac{1}{4}$ on N. face with pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
60.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
78.00	Intersect the W. bdy. of Tp. at the closing corner to secs. 18 and 19, T. 1 N., R. 33 E., which is a basalt stone, 10x8x7 ins., 7 ins. in the ground, marked C C on E. face, with 3 notches on N. and S. edges, with pits, 18x18x12 ins., N. S. and E. of stone, $5\frac{1}{2}$ ft. dist., and mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it. I marked the letters D R on E. face.  Land, mostly level.  Soil, 2nd rate and ashy. Grass and weeds.