

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 19
	18 x 18 x 12, in each sec., mound of earth 2 ft. high, 4½ ft. base over it. I marked stone D R on E. face.
4.80	Trail, course N.W.
30.80	Summit, course W.
33.50	Gulch, course W.
39.60	Set stone, 9x8x7 ins., 6 ins. in the ground, for ¼ sec. corner marked ¼ on W. face and D R on E. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
41.34	Intersect the ¼ sec. corner on E. bdy. of sec. 24, T. 1 N., R. 32 E., which is a basalt stone, 14x12x8 ins., 10 ins. in the ground, marked ¼ on W. face. Pits, 18x18x12 ins., N. and S. of corner, 5½ ft. dist., and mound of earth 1½ ft. high, 3½ ft. base over it. I marked stone D R on E. face.
56.80	Summit of hill.
61.80	Gulch, course W.
79.20	To the E. corner to secs. 19 and 30, T. 1 N., R. 33 E., which is a basalt stone, 9x8x7 ins., 6 ins. in the ground, marked C C on E. faces, with 2 notches on S. and 4 notches on N. edges with pits, 18x18x12 ins., N., E. and S. of stone, 5½ ft. dist., and mound of earth 2 ft. high, 4½ ft. base over it. I marked stone D R on E. face.
	Land, rolling.
	Soil, 3rd rate.
	Bunch grass and sage brush.
	North between secs. 19 and 20.
	Var. 20°00'E.
20.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.