

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	<p style="text-align: center;">Sec. 19</p> <p>18x18x12 ins., E. and W. of stone, 5<math>\frac{1}{2}</math> ft. dist., and raised a mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it.</p>
40.00	<p>To the 1/16 sec. corner between secs. 19 and 20.</p> <p>Land, level and barren.</p> <p>Soil, ashy.</p>
78.30	<p>From the <math>\frac{1}{4}</math> sec. corner between secs. 19 and 20.</p> <p>I run</p> <p>West on random line in sec. 19.</p> <p style="text-align: center;">Var. 20° East.</p> <p>Setting temporary corners at 20, 40 and 60 chains, and at</p> <p>Intersect the West boundary of Township, 24 lks. S. of the <math>\frac{1}{4}</math> sec. corner on West bdy. of sec. 19.</p> <p>Thence I run</p> <p>S. 89° 50' E. on true line through the center of sec. 19.</p> <p style="text-align: center;">Var. 20° East.</p>
18.30	<p>Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5<math>\frac{1}{2}</math> ft. dist., and raised mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it.</p>
38.30	<p>Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for <math>\frac{1}{4}</math> sec. corner marked <math>\frac{1}{4}</math> on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5<math>\frac{1}{2}</math> ft. dist., and raised mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it.</p>
41.30	<p>Trail, course North.</p>
58.30	<p>Deposited charred stake, 12 ins. in the ground, for 1/16 sec. corner. Dug pits, 18x18x12 ins., E. and W. of corner, 5<math>\frac{1}{2}</math> ft. dist., and raised mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it. In E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
78.30	<p>To the <math>\frac{1}{4}</math> sec. corner between secs. 19 and 20.</p> <p>Land, mostly level.</p> <p>Soil, ashy.</p> <p>Weeds, grass and grasshoppers.</p>

June 19, 1889.