

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 20
4.00	Gulch, course N.W.
20.00	Set basalt stone, 10x7x5 ins., 7 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
40.00	To the old ¼ sec. corner, which is a basalt stone, 9x8x7 ins., 6 ins. in the ground, marked ¼ on W. face. Pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and mound of earth 1½ ft. high, 3½ ft. base over it.
47.00	Gulch, course N.W.
60.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
80.00	The corner to secs. 16 and 17, 20 and 21. Land, rolling. Soil, ashy. Grass and weeds.
	From the 1/16 sec. corner, 20 chs. N. of the corner to secs. 19, 20, 29 and 30.
	I run
	N.89°55'E. on random line through the S.½ of section 20. Var. 20°30'E.
	Setting temporary corners at 20, 40 and 60 chains, and at
79.85	Intersect the East bdy. of sec. 20, 20 lks. N. of 1/16 sec. corner, 20 chs. N. of corner to secs. 20, 21, 28 and 29.
	Thence I run
	N.89°56'W. on true line through the S.½ of sec. 20. Var. 20°00'E.
	Descend flat.
19.92	Set basalt stone, 11x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits,