

## Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 20
	18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
29.00	Gulch, course N.W. Deep ditch.
37.00	Draw, course N.
39.84	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., raised a mound of earth 1½ ft. high, 3½ ft. base over it.
59.76	Set a basalt stone, 10x9x6 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
79.85	To the 1/16 sec. corner, 20 chs. North of corner to secs. 19, 20, 29 and 30. Land, mostly level. Soil, 2nd and 3rd rate. Very little grass.
	From the ¼ sec. corner between secs. 19 and 20. I run N.89°55'E. on random line through the center of sec. 20. Var. 20°E. Setting temporary corner at 20, 40 and 60 chains and at 79.80 Intersect the East bdy. of sec. 20, 20 lks. N. of ¼ sec. corner between secs. 20 and 21. Thence I run S.89°56'W. on true line through the center of sec. 20. Var. 21°E.
19.95	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of <sup>stone</sup> stake, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it. ✓