

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 20
29.50	Gulch, course N.W.
39.90	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. corner marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
44.00	Draw, course N.W.
59.85	Deposited charred stake, 12 ins. in the ground, for $\frac{1}{16}$ sec. corner. Dug pits, 18x18x12 ins., E. and W., $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. In E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{16}$ S on N. face.
79.80	Draw, course N.W.
" "	To the $\frac{1}{4}$ sec. corner between secs. 19 and 20. Land, rolling gently. Soil, 2nd rate. Grass and weeds.
80.00	From the $\frac{1}{16}$ sec. corner 20 chains N. of $\frac{1}{4}$ sec. corner between secs. 19 and 20. I run N.89°55'E. on random line through the N. $\frac{1}{2}$ of sec. 20. Var. 21°East. Setting temporary corners at 20, 40 and 60 chains, at Intersect the East bdy. of sec. 20, 25 lks. N. of the $\frac{1}{16}$ sec. corner, 20 chains N. of $\frac{1}{4}$ sec. corner between secs. 20 and 21. Thence I run N.89°54'West on true line through N. $\frac{1}{2}$ of sec. 20. Var. 21°East.
20.00	Set a basalt stone, 10x8x7 ins., 6 ins. in the ground, for $\frac{1}{16}$ sec. corner marked $\frac{1}{16}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
40.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{16}$ sec. corner marked $\frac{1}{16}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., raised