

Subdivisions and Allotments of T. 1 N., R. 33 E.

Chains	Sec. 21
80.00	Setting temporary corners at 20, 40 and 60 chains, and at Intersect East boundary of sec. 21, 12 lks. N. of 1/16 sec., 20 chs. N. of corner to secs. 21, 22, 27 and 28. Thence I run N.89°35'W. on true line through S. $\frac{1}{2}$ of sec. 21. Var. 21° East.
12.00	Summit, course N.W.
20.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
29.75	Road, course N. and S.
40.00	Set basalt stone, 10x7x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
50.00	Road, course N. and S.
60.00	Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18 x12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
80.00	To the 1/16 sec. corner, 20 chs. N. of the corner to secs. 20, 21, 28 and 29. Land, rolling. Soil, 1st and 2nd rate. Grass and weeds.
80.00	From the $\frac{1}{4}$ sec. corner between secs. 20 and 21. I run S.89°40'E. on random line through center of sec. 21. Var. 21° E. Setting temporary corners at 20, 40 and 60 chs., and at Intersect the East bdy. of sec. 21, 15 lks. N. of the $\frac{1}{4}$ sec. corner between secs. 21 and 22. Thence I run