

Base Line of T. 1 N., R. 34 E.
 Surveyed by Timothy W. Davenport under contract No.102.
 Dated July 20, 1863.

Chains	Thence East on South boundary of sec. 31. Var. 20°15'E.
40.00	Set qr. sec. post, made mound of rock.
40.25	South point of a rock crag 12 feet. high.
45.50	Bottom of ridge. Enter brush.
49.50	North fork of McKay's Creek, 100 lks. wide, runs S.W.
51.50	Commence to ascend. Leave bottom land.
80.00	Set post corner to secs. 31 and 32, from which A pine, 12 ins. diam., bears S.40°W., 32 lks. dist. A pine, 8 ins. diam., bears N.30°W., 97 lks. dist. A pine, 15 ins. diam., bears N.70°E., 87 lks. dist. Var. 18°30'E.
	Thence East on South boundary of sec. 32. Var. 18°30'East.
10.00	Top of ridge.
40.00	Set qr. sec. post, from which A pine, 9 ins. diam., bears S.30°W., 63 lks. dist. A pine, 16 ins. diam., bears N.80°E., 38 lks. dist.
43.30	A branch, 10 lks. wide, runs N.60°W.
45.00	Commence to ascend ridge.
72.12	A pine, 18 ins. in diam.
80.00	Set post corner to secs. 32 and 33, from which A pine, 13 ins. diam., bears S.2°E., 205 lks. dist. Made mound of earth, drove charred stake as per instructions. Var. 23°45'East. August 7, 1863.
	East on South boundary of sec. 33. Var. 23°45'E.
40.00	Set qr. sec. post in mound of rock.
80.00	Set post corner to secs. 33 and 34, made mound of rock. Var. 21°45'E.
	Soil, unfit for cultivation. Produces bunch grass; destitute of timber.