

North Boundary of T. 1 N., R. 34 E.

Chains	
40.00	Set basalt stone, 15x12x4, for $\frac{1}{4}$ sec. corner.
80.00	Set post and raised stone mound for corner to secs. 2, 3, 34 and 35. Land, hilly. Soil, 1st rate. Good grass.
	North 89° 46' East on true line on North boundary of sec. 2. Var. 21°30'E.
26.25	Brook, 3 lks., flows N.
40.00	Set post for $\frac{1}{4}$ sec. corner, from which A fir, 15 ins. diam., bears N.38° W., 138 lks. " " 12 " " " S.50°E., 100 lks.
80.00	Set post and raised stone mound for cor. to secs. 1, 2, 35 and 36. Land, stony. Some pine timber.
	North 89°46' East on true line on North boundary of sec. 1. Var. 21°30'East.
38.00	LaGrande & Pendleton Wagon road, course N.W. and S.E.
40.00	Set post and raised stone mound for $\frac{1}{4}$ sec. corner.
80.00	To corner to Townships 1 and 2 North, Ranges 34 and 35 East, Willamette Meridian. Land, hilly. Soil, 2nd rate. Some grass. Pine and fir timber. May 8, 1871.
	Subdivisions of T. 1 N., R. 34 E. Surveyed by Z. F. Moody under contract No. 145. Dated April 23, 1871.
	East on true line on South boundary of sec. 30. Var. 22° East.
40.00	Set basalt stone, 14x14x12, for $\frac{1}{4}$ sec. corner.