

## Subdivisions of T. 1 N., R. 34 E.

Chains	North between secs. 8 and 9.
40.00	Set basalt stone, 14x14x8, for $\frac{1}{4}$ sec. corner.
80.00	Set basalt stone, 18x14x8, for corner to secs. 8, 9, 4 and 5.
	Land, hilly.
	Soil, good, 2nd rate.
	Excellent quality of grass. Some fine pine and fir timber.
	East on random between secs. 4 and 9.
	Var. 20° East.
40.00	Set temporary $\frac{1}{4}$ sec. corner.
80.04	Intersected N. and S. line, 14 lks. S. of corner.
	S. 89° 54' West on true line.
40.02	Set basalt stone, 16x14x8, for $\frac{1}{4}$ sec. corner.
80.04	To corner.
	Land, hilly.
	Soil, good, 2nd rate. First rate quality of grass.
	There is no timber on this line.
	North on random between sections 4 and 5.
40.00	Set temporary $\frac{1}{4}$ sec. corner.
80.50	Intersected North boundary, 15 lks. East of corner.
	S. 00° 6' E. on true line.
40.50	Set basalt stone, 14x14x9, for $\frac{1}{4}$ sec. corner.
80.50	To corner.
	Land, hilly.
	Soil, good, 2nd rate.
	Fine grass.
	May 10, 1871.
	North between secs. 29 and 30.
40.00	Set basalt stone, 18x14x8, for $\frac{1}{4}$ section corner.
80.00	Set basalt stone, 16x12x12, for corner to sections 29, 30, 19 and 20.
	Land, mountainous.
	Soil, 2nd rate. Good grass.