

Subdivisions of T. 1 N., R. 34 E.

Chains	East on random between secs. 20 and 29. Var. 20° E.
40.00	Set temporary $\frac{1}{4}$ section corner.
80.08	Intersected N. and S. line, 12 lks. S. of corner. S. 89° 55' W. on true line.
40.04	Set basalt stone, 18x10x10, for $\frac{1}{4}$ section corner.
80.08	To corner. Land, mountainous. Soil, 2nd rate. Good grass.
	West on random between sections. 19 and 30.
40.00	Set temporary $\frac{1}{4}$ section post.
80.14	Intersected N. and S. line at corner. East on true line.
40.14	Set basalt stone, 14x14x10, for $\frac{1}{4}$ section post.
80.14	To corner. Land, hilly. Soil, 2nd rate. Some good grass.
	North between secs. 19 and 20.
40.00	Set basalt stone, 16x14x10, for $\frac{1}{4}$ sec. corner.
80.00	Set post and made stone mound for corner to sections 17, 18, 19 and 20. Land, hilly. Soil, 2nd rate. Good grass.
	East on random between secs. 17 and 20. Var. 20° 30' E.
40.00	Set temporary $\frac{1}{4}$ sec. corner.
80.10	Intersected N. and S. line, 12 S. of corner. S. 89° 55' W. on true line.
40.05	Set basalt stone, 16x14x10, for $\frac{1}{4}$ sec. cor.
80.10	To corner. Land, hilly; Good grass. Soil, 2nd rate. Some pine timber.