

Subdivisions of T. 1 N., R. 34 E.

Chains	Soil, 2nd rate. Good grass. Some pine timber.
	North between secs. 7 and 8. 2.00 Brook, 4 lks. wide, flows E. 40.00 Set basalt stone, 17x14x12, for $\frac{1}{4}$ sec. corner. 80.00 Set basalt stone, 18x14x4, for corner to secs. 5, 6, 7, 8. Land, hilly. Soil, 2nd rate. Good grass. No timber on this line.
	East on random between secs. 5 and 8. Var. 20°E. 40.00 Set temporary $\frac{1}{4}$ section corner. 80.08 Intersected N. and S. line, 25 N. of cor. N.89°50'W. on true line. 40.04 Set basalt stone, 14x14x9, for $\frac{1}{4}$ sec. corner. 80.08 To corner. Land, hilly. Soil, 2nd rate. Good grass.
	West on random between secs. 6 and 7. 40.00 Set temporary $\frac{1}{4}$ sec. corner. 80.10 Intersected N. and S. line, 12 lks. S. of cor. S.89°55'E. on true line. 40.10 Set basalt stone, 14x14x8, for $\frac{1}{4}$ S. corner. 80.10 To corner. Land, hilly. Soil, 2nd rate. Good grass.
	North on random between secs. 5 and 6. 40.00 Set temporary $\frac{1}{4}$ sec. corner. 80.54 Intersected North boundary, 10 lks. East of corner. S.00°04'E. on true line. 40.54 Set basalt stone, 14x12x10, for $\frac{1}{4}$ section corner. 80.54 To corner.