

Base Line of T. 1 N., R. 34 E.

Chains 40.00	Set basalt stone, 10x9x8 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked S C $\frac{1}{4}$ on N. face and raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
80.00	Set basalt stone, 18x14x8 ins., 12 ins. in the ground, for cor. to secs. 33 and 34 marked S C with 3 notches on E. and W. edges, and raised mound of stone 2 ft. high, $4\frac{1}{2}$ ft. base over it. Land, level. Soil, 1st rate. Fine pasture land.
	Thence S.89°54'W. on true line, S. bdy. sec. 33. Var. 20°15'East. Leave table land and descend.
12.50	Canyon, course S. Ascend.
40.00	Set basalt stone, 24x12x6 ins., 18 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked S C $\frac{1}{4}$ on N. face, and raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Descend ridge sloping West.
80.00	Set basalt stone, 12x12x12 ins., 8 ins. in the ground, for cor. to secs. 32 and 33 marked S C with 4 notches on E., and 2 notches on W. edges, from which A pine, 16 ins., bears S.45°W., 300 lks. dist., marked $\frac{1}{4}$ S S C. B T. No other tree in limits. Raised a mound of stone over it. Land, very rough and mountainous. 80 chs. Soil, 3rd rate, rocky. Bunch grass. No timber. June 11, 1887.
	Thence S.89°54'W. on true line, S. bdy. sec. 32. Var. 21° East. Descend.
24.00	Dry gulch, course S.W.