

North Boundary of T. 1 N., R. 34 E.

Chains	<p>Raised a mound of stone alongside. Pits impracticable. Land, rolling. Soil, 3rd rate. Scattering pine timber with some underbrush.</p>
	<p>South 89°32' W. on N. bdy. sec. 2. Var. 20°10'E.</p>
7.00	Road, course S.W.
37.50	Hollow, course N.W.
40.00	<p>Set a basalt stone, 18x16x14 ins., 12 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, from which A pine, 14 ins. in diam., bears N.55°E., dist. 89 lks. marked $\frac{1}{4}$ S B T. A pine, 18 ins. in diam., bears S. 56°W., dist. 28 lks. marked $\frac{1}{4}$ S B T.</p>
60.00	Gulch, course N.
80.00	<p>Set a basalt stone, 16x14x12 ins., 11 ins. in the ground, for cor. to secs. 2, 3, 34 and 35, marked 2 notches on E. and 4 on W. edges, from which A pine, 16 ins. in diam., bears N.13°E., dist. 84 lks. marked T 2 N S 35 B T. A pine, 10 ins. in diam., bears S.87°E., dist. 140 lks. marked R 34 E S 2 B T. A pine, 16 ins. in diam., bears S.5°W., dist., 46 lks. marked T 1 N S 3 B T. A pine, 16 ins. in diam., bears N.12°W ., dist., 163 lks. marked S 34 B T.</p>
	<p>Land, rolling. Scattering pine timber; thick underbrush. 80 chs. Soil, 2nd rate.</p>
	<p>South 89°32'W. on N. bdy. sec. 3. Var. 20°45'E.</p>
	Leave timber.
35.00	Begin to descend.