

North Boundary of T. 1 N., R. 34 E.

Chains	South 89°32 'W. on N. bdy. Sec. 5. Var. 19°E.
37.50	Canyon, course N.
40.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Raised a mound of stone alongside. Pits impracticable.
49.00	Summit of point.
53.00	Gulch, course N.
64.00	Summit, course N.W.
78.00	Gulch, course N.
80.00	Set a basalt stone, 12x9x7 ins., 8 ins. in the ground, for cor. to secs. 5, 6, 31 and 32, marked 5 notches on E. and 1 on W. edges. Raised a mound of stone alongside. Pits impracticable.
	Land, mountainous. 80 chs.
	Soil, 3rd rate.
	No timber. Good bunch grass.
	South 89° 32'W. on N. bdy. sec. 6. Var. 20° E.
1.50	Gulch, course N.E.
40.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Raised mound of stone alongside. Pits impracticable.
43.00	Pendleton and LaGrande Wagon road, course N.W. and S.E.
67.90	Gulch, course N.W.
84.00	To cor. to Tps. 1 and 2 N., R. 33 and 34 E.
	Land, mountainous. 84 chs.
	Soil, 2nd rate.
	Good grass.
	No timber.