

## North Boundary of T. 1 N., R. 34 E.

Chains

## General Description

This Township is rough and mountainous. Land generally rocky and good only for grazing. There is some good timber in the canyons and one fine body on the uplands in the North Western part. No settlers.

August 9, 1887.

Exterior Lines of T. 1 N., R. 35 E.  
Surveyed by Currin and Noland under special contract.  
Dated May 4, 1887.

(West Boundary)

Beginning on Base Line at the cor. to Tps. 1 N., R. 34  
and 35 East I run

North on true line between Tps. 34 and 35 East and secs.  
31 and 36.

Var. 23°30'E.

30.00 Leave Table land and descend.

40.00 Set a basalt stone, 20x12x12 ins., 15 ins. in the ground,  
for  $\frac{1}{4}$  sec. cor. marked  $\frac{1}{4}$  on W. face, from which

A pine, 20 ins. in diam., bears N. 52 $\frac{1}{2}$ °W., 43 lks.  
dist., marked  $\frac{1}{4}$  S B T.

No other tree in limits.

Raised a md. of stone alongside. Pits impracticable.

52.75 N. fork McKay Creek, 20 lks. wide, course W.

62.50 Bluff of rock, 20 ft. high.

75.00 Table land.

80.00 Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for  
cor. to secs. 25, 30, 31 and 36, marked 1 notch on S.  
and 5 notches on N. edges, from which

A pine, 40 ins. in diam., bears N. 30°E., 29 lks.  
dist., marked T 1 N S 30 B T.

A pine, 15 ins. in diam., bears S. 82°E., 285 lks.  
dist., marked R 35 E S 31 B T.

A pine, 12 ins. in diam., bears S. 48°W., 65 lks.  
dist., marked S 36 B T.

A pine, 12 ins. in diam., bears N. 88°W., 42 lks.  
dist., marked R 34 E S 25 B T.