

West Boundary of T. 1 N., R. 35 E.

Chains

on S.E., T. 2 N. S. 31 on N.E., T 2 N R 34 E S 36
on N.W., T 1 N R 34 E S 1 on S.W., and 6 notches on N.
S. E. and W. edges, from which

A fir, 14 ins. in diam., bears S.10°E., dist. 171
lks., marked T 1 N R 35 E S 6 B T.

A fir, 14 ins. in diam., bears S.70°W., dist. 67 lks.
marked R 34 E S 1 B T.

A pine, 24 ins. in diam., bears N.60°W., dist. 112
lks. marked T 2 N R 34 E S 36 B T.

No other tree in limits.

Land, rolling.

Soil, 2nd rate.

Scattering pine, fir and tamarack timber in hollows.

Good grass.

June 14, 1887.

General Description

Land in this Township is mountainous with good timber in
some places. It is well watered and suitable chiefly
for grazing.

Subdivisions of T. 1 N., R. 34 E.
Surveyed by Currin and Noland under special contract.
Dated May 4, 1887.

From corner to secs. 35 and 36 on South bdy. of Township

I run

North between secs. 35 and 36.

Var. 21° E.

Descend.

23.50 McKay Creek, water in holes, course W.

40.00 Set stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{2}$ sec.
cor. marked $\frac{1}{2}$ on W. face and raised a mound of stone
over it. Cor. on side of mountain face in S.W.

50.00 Top of mountain.

59.00 Descend.

65.00 Bottom of canyon, course S.W.